Items of work	Per	Quantity
Kitchen block—concld.		
Teak-wood finials	Each	2
Silicate painting	Sqr.	5·88
Flooring with Cuddapah slabs over 3" concrete and cement painting	"	4·00
Flooring with Mangalore tiles	"	1·50
Burnt brick in chunam coping	R. ft.	24
Chunam painting	Sqr.	3·09
Constructing chimneys	Lump sum	2
Stables.		
Earthwork excavation	C. yd.	27
Burnt brick in mortar	C. ft.	1,097
Burnt brick in clay	"	1,099
Burnt stone slab 6" thick	S." ft.	111
Chunam plastering	Sqr.	25·29
White and colourwashing	"	25·29
Teakwood wrought and put up with wood oiling	C." ft.	129·72
Roofing with 1st class Mangalore tiles with teak reepers	Sqr.	8·08
Ridge tiles	R. ft.	39
Teakwood battened doors with frames 4"×3" with hinges lock and key	S. ft.	18
Teakwood battened ventilators	"	18
Teakwood windows	"	12
Teakwood gate with bolts, hinges, etc.	"	72
Teakwood ornamental eave board	R." ft.	119
Teakwood pendants	Each	4
Teakwood finials	"	2
Silicate painting	Sqr.	2·40
Flooring with Cuddapah slabs	"	·96
Chunam painting	"	1·55
Latrine.		
Earthwork excavation	C. yd.	3
Burnt brick in mortar	C. ft.	183
Burnt brick in clay	"	177
Burnt stone slabs 6" thick	S." ft.	2
Chunam plastering	Sqr.	5·33
White and colour washing	"	5·33
Cuddapah slab flooring on 3" concrete bed and cement painting	"	67
Burnt brick in chunam coping	R." ft.	40

Abstract Notification.

The attention of the public is invited to the advertisement in detail published in *Mysore Gazette*, dated 30th May 1918, calling for tenders for repairing the temple of Sri Mallikarjunaswami at Bettadapur, Hunsur Taluk.

Y. ASWATHANARAYANA RAO,
Executive Engineer.

No. 5. YEDATORE DIVISION.

Notice.

Notice is hereby given that a bill for work done by piece workers Yeerigadindal Subbaboyee and Muddle Koppal Puttasamachari conjointly on the "Deviation of Yelwal-Hassan road has been prepared by the Sub-Divisional Officer and submitted to this office with a report that the whereabouts of the parties are not known. It is therefore hereby notified that the parties should intimate their whereabouts to this office within two months from the date for needful action being taken in the matter, failing which, steps will be taken to credit the amount of the bill to "revenue".

B. N. ARADHYA,
Executive Engineer.

MYSORE HEADQUARTER RANGE.

Abstract Notification.

Reference is invited to the Notification calling for tenders for the construction of a swimming pond below the Kukkarahalli Tank Bund in Mysore, published in pages 477 and 478 of the *Mysore Gazette*, dated the 30th May 1918.

B. SUBBA RAO,
Sub-Assistant Engineer.

HASSAN DIVISION.

Dated 25th May 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 10th July 1918, for restoring Halwagal-Dodkere, Registered No. 120, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Halwagal-Dodkere, Registered No. 120, Hassan Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detail abstract estimate of Halwagal-Dodkere, Registered No. 120 of Hassan Taluk.

Serial No.	Items of work	Per	Quantity
	Bund R. L. 56·00 top width 6 feet.		
1	Earthwork, raising bund including cutting steps and grips watering and tamping, etc.	C. yd.	75·50
2	Turfing	S. yd.	14,794
3	New grade stones, complete	No.	26
4	Index stones	"	26
5	B. M. stones	"	2
6	Year and date stone	"	1
7	Gauge stone	"	1
8	Registered number stone	"	1
	Sluice (old.)		
9	Repairing the existing sluice	L. S. Rs.	
	Sluice (new).		
10	Earthwork cutting bund	C. yd.	309
11	Excavating foundation	"	17
12	Burnt brick in surki	C. ft.	784
13	Burnt stone slabs 4" thick	S. ft.	143
14	Do 6" do		157
15	Concreting	C. ft.	89
16	Providing plug and rod	L. S. Rs.	
17	Driling holes	No.	4
18	Earthwork refilling	C. yd.	180
19	Surki plastering	Sqr.	4·00
	Weir.		
20	Earthwork clearing high ground excavating foundation cutting draft channel, etc.	L. S. Rs.	
21	Surki concrete	C. ft.	356
22	Burnt brick in surki	"	1,744
23	Burnt stone slabs	S. ft.	179
24	Rough stone work	C. yd.	273
25	Filling boulders, jelly, etc.	"	15
26	Surki plastering	Sqr.	2·00

R. W. SCALDWELL,
Executive Engineer.

SHIMOGA DIVISION.

Dated 21st May 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 1st July 1918, for opening out Channagiri-Sivani road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,600 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for opening out a road from Channagiri to Shivani" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.